

145.60

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22684-00-00
Spot: SWNW Sec/Twnshp/Rge: 33-15S-25W
1980 feet from N Section Line, 500 feet from W Section Line
Lease Name: BASINGER Well #: 2
County: TREGO Total Vertical Depth: 4480 feet

Operator License No.: 6030
Op Name: AINSWORTH OPERATING CO.
Address: 4676 COMMERCIAL ST., SE #412
SALEM, OR 97302

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/06/2010 8:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KELLY WILSON Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DAVID WANN WitnessType: NONE
Date/Time Plugging Completed: 10/06/2010 9:15 PM KCC Agent: DAVID WANN

Actual Plugging Report:

1st. Plug at 1900' w/25 sxs.
2nd. Plug at 875' w/100 sxs.
3rd. Plug at 270' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

12/7/10
2010/10/23

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed  (TECHNICIAN)

CM

RECEIVED Form CP-2/3

NOV 01 2010

KCC WICHITA

OCT 28 2010