

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20524-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 24-14S-11W
2310 feet from N Section Line, 330 feet from W Section Line
Lease Name: SEBESTA A Well #: 1
County: RUSSELL Total Vertical Depth: 2159 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	212	0	160 SX
PROD	5.5	2159	0	60 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2010 12:30 PM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 483-1821

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 400# hulls.
Perf 1200' - 500' - 200'.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/05/2010 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 1936' - pumped 100 sxs cement with 300# hulls.
Pulled tubing to 936' - pumped 85 sxs cement with 100# hulls - cement circulated.
POOH. Hooked up to casing and pumped 30 sxs cement - circulated out the Braden head.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4548.

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

RECEIVED

Form CP-2/3

OCT 12 2010

OCT 07 2010

KCC WICHITA