

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20564-00-02
Spot: NWNESENE Sec/Twnshp/Rge: 26-15S-9W
3751 feet from S Section Line, 346 feet from E Section Line
Lease Name: SHANELEC B Well #: 1
County: ELLSWORTH Total Vertical Depth: 3200 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2700		
CIBP	4.5	3017		
SURF	8.625	250		150 SX
PROD	4.5	3094		100 SX

Well Type: SWD UIC Docket No: _____ Date/Time to Plug: 09/20/2010 10:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN BUEHLER Company: TRANS PACIFIC OIL CORP Phone: (785) 483-1821

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/20/2010 2:45 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM, SET CIBP @ 2700' AND CAP WITH 2 SX'S CEMENT.
PERFORATE @ 1000', 700', AND 300'. RUN TUBING TO 1000' AND PUMP 35 SX'S
CEMENT. PULL TUBING TO 700' AND PUMP 35 SK'S CEMENT. PULL TUBING TO
300' AND CIRCULATE CEMENT TO SURFACE. SHUT VALVE ON PROD. CASING
AND PUMP CEMENT UP SURFACE CASING. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
2764	2774	CSG	
2754	2758	CSG	

Remarks: PERF TECH TICKET 7614. 60-40 OZ. 4% GEL. QUALITY WELL CEMENTING TICKET 4245. USED 200 SX'S CEMENT.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

RECEIVED

OCT 20 2010

Form CP-2/3

KCC WICHITA