

15145.60

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-10075-00-01
Spot: NWNWNE Sec/Twnshp/Rge: 27-25S-16W
5147 feet from S Section Line, 2317 feet from E Section Line
Lease Name: CUDNEY B Well #: 2
County: EDWARDS Total Vertical Depth: 4480 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	447		WITH 300 SX CMT
PROD	4.5	3830	710	WITH 150 SX CMT

Well Type: SWD UIC Docket No: D20723.0 Date/Time to Plug: 07/21/2010 9:30 AM
Plug Co. License No.: 30481 Plug Co. Name: APOLLO ENERGIES, INC.
Proposal Rcvd. from: JIM BYERS Company: APOLLO ENERGIES, INC. Phone: (620) 672-9001

Proposed Plugging Method: SAND BOTTOM TO 3400' & 4 SX CMT. PERFORATE OR PULL CASING @ 1050'. PLUG AT 1050' WITH 15 SX GEL & 50 SX CMT. PLUG AT 480' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/21/2010 3:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3400' & 4 SX CMT WITH DUMP BAILER. PERFORATED 4 1/2" @ 1050'. RAN TBG TO 1070'. PUMPED 15 SX GEL & 50 SX CMT. PULLED TBG TO 460' & PUMPED 50 SX CMT. PULLED TBG TO 60' & PUMPED 20 SX CMT. GOOD CIRCULATION THROUGHOUT JOB.

Perfs:

Top	Bot	Thru	Comments
3450	3580		TOPEKA

12/07/10
2011060288

Remarks: USED 60/40 POZMIX 4% GEL QUALITY WELL SERVICE PUMPED ALLIED'S CEMENT.

Plugged through: TBG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
JUL 22 2010
KCC DODGE CITY

RECEIVED
AUG 04 2010
KCC WICHITA
Form CP-2/3