

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-22187-00-00
Spot: NWSEENENW Sec/Twnshp/Rge: 16-30S-6W
4405 feet from S Section Line, 3245 feet from E Section Line
Lease Name: MESSENGER Well #: 1-16
County: KINGMAN Total Vertical Depth: 4125 feet

Operator License No.: 31337
Op Name: WILDCAT OIL & GAS LLC
Address: 10286 SW 170TH AVE
NASHVILLE, KS 67112

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	216		150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 33902 Plug Co. Name: HARDT DRILLING LLC
Proposal Rcvd. from: GARY ADELHARDT Company: WILDCAT Phone: _____

Proposed Plugging Method: 35 SXS 1150', 35 SXS 750', 35 SXS 266', 25 SXS @ 60'. 15 SXS RH.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 05/07/2009 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report: _____ Perfs: _____

RAN DRILL PIPE OPEN END TO 1150' & SPOTTED 35 SXS CMT, PULL DRILL PIPE TO 750' & SPOTTED 35 SXS CMT. PULLED DRILL PIPE TO 266' & SPOTTED 35 SXS CMT. PULL DRILL PIPE TO 60' AND SPOTTED 25 SXS CIRCD. 15 SXS IN RAT HOLE.

Remarks: ALLIED CEMENT 60/40 4% GEL

Plugged through: DP

District: 02

Signed _____
(TECHNICIAN)

RECEIVED
OCT 12 2010
Form CP-2/3
KCC WICHITA

JK