

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01102-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 6-9S-16W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HUTTON A Well #: 1
County: ROOKS Total Vertical Depth: 3434 feet

Operator License No.: 33759
Op Name: WINELAND OIL - LLC
Address: 304 N 3RD PO BOX 53
OTIS, KS 67565

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	170	0	w/unknown sxs cmt
PROD	4.5	3408	0	w/250 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/23/2010 12:00 PM
Plug Co. License No.: 32247 Plug Co. Name: CRAWFORD, JEFF DBA JEFF'S OILWELL SUPERVISION
Proposal Rcvd. from: LARRY WINELAND Company: WINELAND OIL - LLC Phone: (785) 387-2385

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 300# hulls.
Junk in the hole at 996' - rods and tubing.
Dakota squeeze with 650 sxs cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/23/2010 3:20 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH to 994'. Allied rigged to tubing and pumped 65 sxs cement to circulate cement to surface.
Pulled tubing - rigged to 4 1/2" casing with a swedge and pumped 125 sxs cement with 200# hulls mixed in.
Max. P.S.I. 450#. S.I.P. 200#.
Backside 10" - 4 1/2" casing cemented in with 650 sxs.

Perfs:

Top	Bot	Thru	Comments
3123	3127		
3066	3070		

Remarks: ALLIED CEMENTING COMPANY-TICKET #41927.

Plugged through: TBG

District: 04

Signed _____


(TECHNICIAN) *cm*

RECEIVED

AUG 26 2010

Form CP-2/3

AUG 24 2010

KCC WICHITA

RYAN CONSOLIDATED PETRO. #1 HUTTON

6-9-16W
SW SW NE


Contr. BERGMAN DRILLING

ROCKS County

E. 1915RB Comm. 2/28/63 Comp. 4/18/63 IP PMP 6 BOPD + 2 BOPD
LANS 3066-70, 3123-27

LOG Tops	Depth	Datum
ANH	1229	+686
B/ANH	1265	+650
TOP	2807	-892
HEEB	3026	-1111
TOR	3045	-1130
LANS	3066	-1151
B/KC	3313	-1398
ARB	3374	-1459
LTD	3434	-1519

Casing
10" 170;
4" 3408/250 sx;
o/s 3066-70: 3122-32: 3166-72:
3232-39:
CO: 16/3123-27: 16/3066-70: A
2000: SWB LD: SWB 1 BFPH/4 HRS
(40% OIL): POP:



GEOL-LEE CORNELL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS