

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20339-00-00
Spot: SESENE Sec/Twnshp/Rge: 35-17S-31W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: JANSSEN V Well #: 1
County: SCOTT Total Vertical Depth: 4615 feet

Operator License No.: 7775
Op Name: WILTON PETROLEUM, INC.
Address: PO BOX 391
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4200		WITH 2 SX CMT
CIBP		4285		
SURF	8.625	343		WITH 225 SX CMT
PC		2286		WITH 450 SX CMT
PROD	4.5	4613	0	WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/07/2010 9:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: RENE Company: H-D OILFIELD SERVICE, INC. Phone: (785) 398-2289

Proposed Plugging Method: SAND TO 4200' & 4 SX CMT. RUN TBG TO 2280', CIRCULATE CMT TO SURFACE. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/07/2010 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4200' WITH 2 SX CMT. RUN TBG TO 2273'. CIRCULATE CMT TO SURFACE USING 125 SX CMT. TOOH WITH TBG. TOP OFF 4 1/2" WITH 25 SX CMT. PUMP 50 SX CMT DOWN ANNULUS. SHUT IN PRESSURE 200#.

Perfs:

Top	Bot	Thru	Comments
4366	4368		
4343	4347		
4297	4301		
4252	4254		

RECEIVED
JUL 23 2010
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED

JUL 14 2010

KCC DODGE CITY

Signed

(TECHNICIAN)