

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20682-00-00
Spot: SESENWNW Sec/Twnshp/Rge: 29-20S-11W
4125 feet from S Section Line, 4125 feet from E Section Line
Lease Name: HAGEN UNIT B Well #: 1
County: BARTON Total Vertical Depth: 2648 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	248	0	w/unknown sxs cmt
PROD	5.5	1626	1214	w/unknown sxs cmt

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/28/2010 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: VESS OIL CORPORATION Phone: (620) 562-8088

Proposed Plugging Method: Ordered 290 sxs 60/40 pozmix - 4% gel - 500# hulls.
Shallow gas well.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/28/2010 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement.
Cut casing at 1214' - pulled to 1050' - tied onto casing and pumped 100 sxs cement with 300# hulls.
Pulled casing to 560' - pumped 50 sxs cement with 100# hulls.
Pulled to 320' - pumped 70 sxs cement with 100# hulls - circulated cement to surface.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
1550	1552		WINFIELD
1545	1547		WINFIELD
1518	1522		HERRINGTON

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #36538.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

RECEIVED
JUL 12 2010
Form CP-2/3
KCC WICHITA

JUN 30 2010

