

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-00784-00-00
Spot: NWSENW Sec/Twnshp/Rge: 15-17S-8W
3820 feet from S Section Line, 3820 feet from E Section Line
Lease Name: KASKA A Well #: 3
County: ELLSWORTH Total Vertical Depth: 3286 feet

Operator License No.: 31327
Op Name: PAULEY, GARY DBA PAULEY OIL
Address: 314 5TH ST
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	198		
PROD	5.5	3283		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/14/2011 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: GARY PAULEY Company: PAULEY OIL Phone: (785) 252-8024

Proposed Plugging Method: ATTEMPT MADE TO GET TO BOTTOM--NOT SUCCESSFUL, ENCOUNTERED METAL SHAVINGS AT 2850'. PERFORATE AT 1050', 750', AND 250'. RUN TUBING TO 2850' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 1050' AND PUMP 35 SX'S--LET SET AND TAG. PULL TUBING TO 750' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 250' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/14/2011 1:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, ATTEMPT MADE TO GET TO BOTTOM WITH POWER SWIVEL--
ENCOUNTERED STEEL SHAVINGS, COULDN'T GET THRU 2850'. THIS ABAN'D
WELL HAD BEEN DENIED TA STATUS DUE TO HIGH FLUID LEVEL. EMERGENCY
PLUGGING APPLIED FOR AND PERMITTED BY JEFF KLOCK. PERFORATE AT 1050',
750' AND 250'. RUN TUBING TO 2850' AND PUMP 50 SX'S CEMENT. PULL TUBING
TO 1050' AND PUMP 35 SX'S CEMENT WITH 6% CC, PULL TUBING TO 750' AND LET
CEMENT SET TO TAG. TAGGED CEMENT WITH TUBING AT 900'. PULL TUBING
TO 750' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 250' AND CIRCULATE
CEMENT TO SURFACE. OPERATOR HAD CUT A WINDOW ON SURFACE CASING--
REVEALING CEMENT PRESENT. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3257	3286	CSG	

Remarks: 60-40 POZ, 4% GEL. QUALITY CEMENT TICKET #4773. USED APPROX. 155 SX'S CEMENT. PIONEER WIRELINE TICKET 33448.

Plugged through: TBG

District: 02

Signed _____

Virgil Clothier
(TECHNICIAN)

RECEIVED

✓ APR 05 2011

KCC WICHITA