

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22354-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 19-29S-15W
2343 feet from N Section Line, 2290 feet from E Section Line
Lease Name: LEE Well #: 1
County: PRATT Total Vertical Depth: 5080 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN STE 420
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4700 | | WITH 2 SX CMT |
| SURF | 10.75 | 285 | | WITH 275 SX CMT |
| PROD | 5.5 | 5072 | 2300 | WITH 200 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/02/2011 10:00 AM
Plug Co. License No.: 33939 Plug Co. Name: BLACKGOLD OILFIELD SERVICE LLC
Proposal Rcvd. from: ROBIN BROWN Company: LOTUS OPERATING Phone: (620) 546-4801

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/02/2011 11:10 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD @ 5021'. SET CIBP @ 4700' & PUT 2 SX CMT ON TOP OF CIBP. 1ST PLUG AT 945' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 75 SX CMT. 3RD PLUG AT 60' WITH 25 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|-------------|
| 4735 | 4770 | | MISSISSIPPI |

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED
MAR 18 2011
KCC WICHITA

District: 01

Signed

Stephen J Pfeifer
(TECHNICIAN)

RECEIVED
MAR 14 2011
KCC DODGE CITY

Form CP 27