

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-06852-00-00  
Spot: NENESW Sec/Twnshp/Rge: 9-14S-14W  
2310 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: SOLBACH (RUSCH) Well #: 2  
County: RUSSELL Total Vertical Depth: 3087 feet

Operator License No.: 30737  
Op Name: M.A. YOST OPERATIONS, INC  
Address: 30 N BROOKS PO BOX 811  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	355	0	200 SX
PROD	4.5	3087	0	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/22/2011 3:00 PM  
Plug Co. License No.: 34147 Plug Co. Name: ACE WELL SERVICE, INC.  
Proposal Rcvd. from: JACK YOST Company: M.A. YOST OPERATIONS, INC. Phone: (785) 483-6455

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 700# hulls - 8 sxs gel.  
Hole in casing at 555' - 557'.  
Perf: 1500' - 850'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/23/2011 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

03/22/2011 - L-K Wire line had trouble getting perf gun thru bad shot in casing.  
Ran tubing and shot thru tubing. RT to 2800'.  
03/23/2011 - Pumped 5 sxs gel - followed with 50 sxs cement.  
Pulled tubing to 1550' - pumped 70 sxs cement with 200# hulls.  
POOH. Pumped 135 sxs cement with 400# hulls - cement circulated out the Braden Head.  
Shut Braden head valve - P.S.I. up casing to 250# - shut in.

Perfs:

Remarks: ALLIED CEMENTING COMPANY-TICKET #36448.

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

RECEIVED  
APR 01 2011  
KCC WICHITA

Form CP-2/3

MAR 30 2011