

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-23606-00-00  
Spot: W2NWNE Sec/Twnshp/Rge: 8-16S-21W  
4589 feet from S Section Line, 2286 feet from E Section Line  
Lease Name: LAMER Well #: 1-8  
County: NESS Total Vertical Depth: 4380 feet

Operator License No.: 8996  
Op Name: MID-CONTINENT RESOURCES, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	220		WITH 135 SX CMT
PC		1690		WITH 300 SX CMT
PROD	5.5	4378	0	WITH 375 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/14/2011 4:30 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: SCOTT CORSAIR Company: MID-CONTINENT RESOURCES Phone: (785) 398-2270

Proposed Plugging Method: PUMP 35 SX CMT & 200# HULLS, THEN GEL SPACER TO ANHYDRITE, THEN CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/15/2011 12:20 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CASING WAS FULL OF WATER. TIED ONTO CASING & PRESSURED TO 1200#. TIED ONTO BACKSIDE & PUMPED 40 SX CMT. PRESSURED TO 500# & HELD. 3/15/11: FOUND BOTTOM HAD BEEN CEMENTED WITH 150 SX CMT. RAN SAND LINE & FOUND CMT AT 2500'. RAN TBG TO 1500' & PUMPED 145 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 10 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4269	4273		CHEROKEE

RECEIVED  
MAR 18 2011  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA 10 YR\*\* USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
MAR 16 2011  
KCC DODGE CITY