

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23416-00-00
Spot: NW Sec/Twnshp/Rge: 8-16S-21W
3929 feet from S Section Line, 3949 feet from E Section Line
Lease Name: LAMER Well #: 2
County: NESS Total Vertical Depth: 4377 feet

Operator License No.: 8996
Op Name: MID-CONTINENT RESOURCES, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	269		WITH 145 SX CMT
PC		1675		WITH 300 SX CMT
PROD	5.5	4376	0	WITH 450 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/14/2011 3:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: MID-CONTINENT RESOURCES Phone: (785) 398-2270

Proposed Plugging Method: PUMP 35 SX CMT & 200# HULLS, THEN GEL SPACER TO ANHYDRITE, THEN CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/14/2011 4:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 35 SX CMT & 200# HULLS, 18 SX GEL THEN 200 SX CMT. MAXIMUM PRESSURE 300#. SHUT IN PRESSURE 0#. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 500# & HELD. TOPPED OFF WITH 60 SX CMT & STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4251	4255		CHEROKEE

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

RECEIVED
MAR 18 2011

KCC WICHITA

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED

MAR 16 2011

KCC DODGE CITY

Form CP-2/3