

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20671-00-00
Spot: NWSEWNNE Sec/Twnshp/Rge: 16-25S-23W
680 feet from N Section Line, 1840 feet from E Section Line
Lease Name: POHLMANN Well #: 16-2
County: FORD Total Vertical Depth: 5407 feet

Operator License No.: 32204
Op Name: REDLAND RESOURCES, INC.
Address: 6001 NW 23RD ST
OKLAHOMA CITY, OK 73127

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4700		WITH 2 SX CMT
SURF	8.625	797		WITH 400 SX CMT
COND	20	60		WITH 75 SX CMT
PROD	4.5	4493	2234	WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/22/2011 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Revd. from: DAVID HICKMAN Company: REDLAND RESOURCES Phone: (580) 334-7013

Proposed Plugging Method: SET CIBP @ 4700' WITH 2 SX CMT. PLUG AT 1530' WITH 15 SX GEL & 50 SX CMT. PLUG AT 830' WITH 50 SX CMT. PLUG AT 390' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/22/2011 10:20 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4700' WITH 2 SX CMT. 1ST PLUG AT 1530' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 850' WITH 50 SX CMT. 3RD PLUG AT 390' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4766	4774		
4756	4766		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED
MAR 30 2011
KCC WICHITA

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
MAR 24 2011
KCC DODGE CITY

Form 108