

TO: ✓  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-25340-00-00  
Spot: S2NWSNW Sec/Twnshp/Rge: 21-16S-11W  
1665 feet from N Section Line, 1650 feet from W Section Line  
Lease Name: NADINE Well #: 1  
County: BARTON Total Vertical Depth: 3334 feet

Operator License No.: 30458  
Op Name: RJM COMPANY  
Address: PO BOX 256  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	436	0	200 SX CMT
TI	2.875	3320		
PROD	5.5	3333	1729	180 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/18/2011 10:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: CHRIS HOFFMAN Company: RJM COMPANY Phone: (620) 587-3600

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/18/2011 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement.  
Shot off casing at 1729' - pulled to 1500' - pumped 125 sxs cement with 300# hulls.  
Pulled to 750' - pumped 30 sxs cement with 100# hulls.  
Pulled to 475' - pumped 40 sxs cement with 100# hulls.  
Pulled to 200' - circulated to surface with 75 sxs cement.  
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3202	3212		
3184	3188		
3164	3174		

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #36395.  
Plugged through: CSG

District: 04 Signed Bruce Rodie (TECHNICIAN) CM

RECEIVED  
MAR 24 2011  
KCC WICHITA  
Form CP-2/3

MAR 22 2011