

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23185-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 16-7S-20W  
4950 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: ROSS Well #: 1  
County: ROOKS Total Vertical Depth: 3623 feet

Operator License No.: 31569  
Op Name: BACH, JASON DBA BACH OIL PRODUC  
Address: PO BOX 723  
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	212	0	160 sx
PROD	5.5	3615	0	240 sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/18/2011 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DALE FERLAND Company: BACH OIL PRODUCTION Phone: (785) 302-1435

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 300# hulls - 11 sxs gel spacer.  
DV Tool at 1699' w/350 sxs cwc.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/18/2011 10:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing - pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls. - followed with 11 sxs gel spacer.  
Pumped 195 sxs 60/40 pozmix - 4% gel with 100# hulls.  
S.I.P. 300#.  
Hooked to 8 5/8" x 5 1/2" annulus - pressured to 500# immediately.

Perfs:

Top	Bot	Thru	Comments
3356	3356		

RECEIVED  
MAR 23 2011  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #34174.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

CM

Form CP-2/3

MAR 21 2011