

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21075-00-00
Spot: SENWSW Sec/Twnshp/Rge: 3-13S-16W
1813 feet from S Section Line, 4401 feet from E Section Line
Lease Name: GERSTNER Well #: SWD
County: ELLIS Total Vertical Depth: 861 feet

Operator License No.: 6246
Op Name: BENNETT & SCHULTE OIL CO., A GEN
Address: 140 W WICHITA AVE
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	210	0	w/125 sxs cmt
T1	2.375	690		
PKR		690		
PROD	5.5	856	0	w/150 sxs cmt

Well Type: SWD UIC Docket No: D18067.0 Date/Time to Plug: 03/16/2011 12:00 PM
Plug Co. License No.: 6246 Plug Co. Name: BENNETT & SCHULTE OIL CO., A GENERAL PARTNERSHIP
Proposal Rcvd. from: FRANK SCHULTE Company: BENNETT & SCHULTE OIL CO., A Phone: (785) 483-2721

Proposed Plugging Method: Ordered 150 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/16/2011 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Rigged to 5 1/2" casing with a swedge - mixed and pumped 150 sxs cement with 500# mixed in.
Max. P.S.I. 400#. S.I.P. 150#.
Dug up 8 5/8" casing - backside was full of cement.

Perfs:

Top	Bot	Thru	Comments
730	750		INJECTION ZONE

RECEIVED
MAR 18 2011
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING-TICKET #4787.

Plugged through: CSG

District: 04

Signed

Patricia Staab
(TECHNICIAN)

cc to H/C *4/7/11*
Form CP-2/3

MAR 16 2011