

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-093-00057-00-00  
Spot: N2S2NENE Sec/Twnshp/Rge: 5-21S-38W  
668 feet from N Section Line, 660 feet from E Section Line  
Lease Name: RUPP Well #: 1  
County: KEARNY Total Vertical Depth: 5175 feet

Operator License No.: 5364  
Op Name: BEREN CORPORATION  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1150		
SURF	8.625	294		WITH 225 SX CMT
PROD	4.5	5175	0	WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/04/2011 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: WAYNE GERSTNER Company: BEREN CORPORATION Phone: (316) 772-1155

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/04/2011 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 25 SX CMT & 100# HULLS @ 4811'. PLUG AT 2300' WITH 50 SX CMT & 100# HULLS. TOOH WITH TBG. CIBP @ 1150'. TEST CASING TO 800# & HELD. PERFORATE @ 1100'. INJECTION RATE 3 BPM @ 400#. PUMPED 180 SX CMT DOWN 4 1/2" CASING @ 400 PSI (105 SX CMT OUT PERFS) LEAVING CASING FULL OF CMT. NO CIRCULATION OR BLOW ON ANNULUS. PUMP 70 SX CMT DOWN ANNULUS TO 250 PSI. HOLDING AT 150#.

Perfs:

Top	Bot	Thru	Comments
4834	4838		MORROW

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_

*Ken Jehlik*  
(TECHNICIAN)

RECEIVED

MAR - 8 2011

KCC DODGE CITY

RECEIVED  
MAR 18 2011  
KCC WICHITA

Form CR-13