

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-21867-01-00  
Spot: N2S2SW Sec/Twnshp/Rge: 5-31S-32W  
937 feet from S Section Line, 4010 feet from E Section Line  
Lease Name: VAUGHN Well #: 1-H5  
County: SEWARD Total Vertical Depth: 5486 feet

Operator License No.: 33127  
Op Name: CHAPARRAL ENERGY, L.L.C.  
Address: 701 CEDAR LK BLVD  
OKLAHOMA CITY, OK 73114

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	9.625	620		WITH 300 SX CMT
L1	4.5	5460		TOP OF LINER @ 2889' LESS MD OF 5486'.
PROD	7	2936	1005	WITH 75 SX CMT

Well Type: HI UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/18/2011 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 2800' WITH 5 SX CMT. PLUG AT 1050' WITH 75 SX CMT. PLUG AT 650' WITH 100 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/18/2011 1:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

RIH W/7" CIBP, UNABLE TO GET BELOW 100'. POOH WITH CIBP & DETERMINED CASING WENT FROM 23# TO 26#. RIH WITH 7" CASING SCRAPER TO 1100'. RIH W/TBG TO 2938' & PUMP 75 SX CMT WITH 200# HULLS. SHUT DOWN 4 HOURS & TAG TOC @ 2720' CIRCULATE HOLE WITH MUD, PRESSURE TEST CASING TO 500 PSI. HELD OK. FREE POINT 7" @ 1100'. SHOT OFF AT 1005' & POOH. RIH W/TBG PUMPED 75 SX 1050'. PUMP 100 SX CMT AT 650'. PUMP 20 SX CMT AT 60'.

Perfs:

Top	Bot	Thru	Comments
5166	5459		
3228	4871		
2933	3144		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

*Jack MacLaskey*  
(TECHNICIAN)

RECEIVED  
MAR 21 2011  
KCC DODGE CITY

RECEIVED  
MAR 28 2011  
KCC WICHITA

Form C-2/3