

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20124-00-00
Spot: NWSE Sec/Twnshp/Rge: 35-23S-40W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease Name: COOK Well #: 2-35
County: HAMILTON Total Vertical Depth: 2500 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	445		WITH 300 SX CMT
PROD	4.5	2499	0	WITH 500 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/02/2011 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/02/2011 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 25 SX CMT & 150# HULLS @ 2405'. PUMP 40 SX CMT & 50# HULLS @ 1900'.
TOOH WITH TBG. RAN BOND LOG. TOC @ 450'. PERFORATE @ 410'. RAN TBG TO
1000' & PUMP 30 SX CMT. TOOH WITH TBG. CIRCULATE CMT THROUGH PERFS @
410' FILLING THE 4 1/2" X 8 5/8" ANNULUS AND THE 4 1/2" CASING TO SURFACE
USING 90 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2430	2440		U WINFIELD

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed _____

Ken Jehlik
(TECHNICIAN)

RECEIVED
MAR - 8 2011
KCC DODGE CITY

RECEIVED
MAR 18 2011
KCC WICHITA

Form C