

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-20540-00-00  
Spot: SWNESE Sec/Twnshp/Rge: 1-22S-41W  
1325 feet from S Section Line, 1250 feet from E Section Line  
Lease Name: BOLTZ Well #: 2A-1  
County: HAMILTON Total Vertical Depth: 2785 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: 6200 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	334		WITH 180 SX CMT
PROD	4.5	2780	0	WITH 725 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/24/2011 2:30 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: RUN TBG TO 2700' & FILL 4 1/2" CASING WITH CMT USING 300# HULLS & 175 SX CMT. ATTEMPT TO PUMP 50 SX CMT DOWN ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/24/2011 5:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 25 SX CMT & 200# HULLS @ 2700'. PUMP 75 SX CMT & 200# HULLS @ 2400'. HOLE CIRCULATED. PUMP 100 SX CMT & 100# HULLS @ 1200'. CIRCULATED CMT TO SURFACE. TOOH WITH TBG. TOP OFF 4 1/2" CASING WITH 15 SX CMT. PUMP 15 SX CMT DOWN ANNULUS. PRESSURE TO 250#.

Perfs:

Top	Bot	Thru	Comments
2738	2748		CHASE


Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED  
MAR 18 2011  
KCC WICHITA

District: 01

Signed



(TECHNICIAN)

RECEIVED  
MAR - 8 2011  
KCC DODGE CITY

Form 11-23