

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-20492-00-00  
Spot: E2NWSW Sec/Twnshp/Rge: 36-4S-20W  
1980 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: LYNCH Well #: 1  
County: PHILLIPS Total Vertical Depth: 3500 feet

Operator License No.: 9067  
Op Name: DAMAR RESOURCES, INC.  
Address: 234 W 11TH STE A PO BOX 70  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3439		
SURF	8.625	250	0	160 SX
PROD	5.5	3458	0	125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/28/2011 10:00 AM  
Plug Co. License No.: 33868 Plug Co. Name: RENEGADE WELL SERVICE LLC  
Proposal Rcvd. from: AVEN WEAVERLING Company: DAMAR RESOURCES, INC. Phone: (785) 623-3221

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 14 sxs gel.  
Removed bridge plug at 3439'.  
DV at 1475' w/300 sxs.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/28/2011 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3316' - pumped 14 sxs gel spacer - followed with 65 sxs 60/40 pozmix - 4% gel with 250# hulls.  
Pulled tubing to 1486' - pumped 150 sxs 60/40 pozmix - 4% gel with 150# hulls to circulate to surface.  
Pulled all tubing. Hooked to 5 1/2" casing - pumped 20 sxs 60/40 pozmix - 4% gel. S.I.P. 450#.  
Hooked to 8 5/8" x 5 1/2" annulus. Pressured immediately.

Perfs:

Top	Bot	Thru	Comments
3174	3177		LKC

RECEIVED  
APR 04 2011  
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4741.

Plugged through: TBG

District: 04

Signed Pat Bedore  
(TECHNICIAN)

CM