

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-00611-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 32-5S-20W  
4950 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: RAY B Well #: 2  
County: PHILLIPS Total Vertical Depth: 3576 feet

Operator License No.: 5088  
Op Name: DARRAH, JOHN JAY, JR.  
Address: 225 N MARKET STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	125	0	w/unknown sxs cmt
PROD 7		3571	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/16/2011 12:30 PM  
Plug Co. License No.: 34115 Plug Co. Name: SCHIPPERS OILFIELD SERVICES, LLC  
Proposal Rcvd. from: MIKE KERNS Company: DARRAH, JOHN JAY, JR. Phone: (785) 623-3780

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 350# hulls - 20 sxs gel spacer.  
Perfed at 1680' and 1075'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/16/2011 5:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3362' - pumped 20 sxs gel spacer - followed with 75 sxs 60/40 pozmix - 4% gel and 200# hulls.  
Pulled tubing to 1710' - pumped 300 sxs 60/40 pozmix - 4% gel with 150# hulls to circulate to surface.  
Pulled all tubing. Topped off 7" casing with 50 sxs 60/40 pozmix - 4% gel.  
Hooked to 10" x 7" annulus - pumped 25 sxs 60/0 pozmix - 4% gel - cement coming out around casing hanger.

Perfs:

Top	Bot	Thru	Comments
3572	3576		OH

RECEIVED  
MAR 23 2011  
KCC WICHITA

Remarks: S.O.S. - TICKET #494.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

Form CP-2/3

MAR 21 2011