

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-00264-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 8-28S-34W
2440 feet from S Section Line, 2466 feet from E Section Line
Lease Name: GOERING Well #: 1
County: HASKELL Total Vertical Depth: 2811 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: 14950 HEATHROW FORREST PKWY P
HOUSTON, TX 77210

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	550		WITH 350 SX CMT
L1	5.5	2811		
PROD	7	2561	0	WITH 900 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/10/2011 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PUMP HULLS & 80 SX CMT @ 2548'. PLUG AT 1800' WITH 50 SX CMT. CUT 7" @ 650'. RIH TBG TO 650' & FILL TO SURFACE.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/10/2011 5:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

Perfs:

****WELL HAS 5 1/2" SLOTTED LINE FROM 2548' TO 2811'.** RIH WITH TBG & TAGGED COLLAPSED CASING @ 1428'. LOADED CASING WITH 40 BBL MUD, PUMPED 200# HULLS & 50 SX CMT. SHUT DOWN 4 HOURS & TAGGED TOC AT 1138'. RAN BOND LOG FROM 1120' TO SURFACE SHOWING CMT TO SURFACE. RIH WITH TBG TO 650' & PUMPED 120 SX CMT. FILLED TO SURFACE.**

RECEIVED
MAR 21 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Jack MacLashy
(TECHNICIAN)

RECEIVED
MAR 17 2011
KCC DODGE CITY

Form CP-275