

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-20817-00-00  
Spot: NESWSWNE Sec/Twnshp/Rge: 17-24S-17W  
3125 feet from S Section Line, 2166 feet from E Section Line  
Lease Name: CROSS W B - B Well #: 2-17  
County: EDWARDS Total Vertical Depth: 4460 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	285		WITH 225 SX CMT
PROD	4.5	4450	1975	WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/11/2011 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/11/2011 1:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND BACK TO 4330' & PUT 4 SX CMT ON TOP OF SAND BRIDGE. 1ST PLUG AT 1190' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 310' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4388	4392		KINDERHOOK SA


RECEIVED  
MAR 21 2011  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA-10YR\*\* USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed

  
(TECHNICIAN)

RECEIVED

MAR 17 2011

KCC DODGE CITY

Form CP-273