

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-20630-00-00  
Spot: SWNESE Sec/Twnshp/Rge: 8-24S-17W  
2284 feet from S Section Line, 420 feet from E Section Line  
Lease Name: HAMMEKE Well #: 1-8  
County: EDWARDS Total Vertical Depth: 4485 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	248		WITH 225 SX CMT
PROD	4.5	4484	2025	WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/04/2011 2:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/04/2011 4:50 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND BACK TO 4275' & PUT 4 SX CMT ON TOP OF SAND BRIDGE. 1ST PLUG AT 1190' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 280' WITH 20 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4376	4388		MISSISSIPPI
4336	4362		CHEROKEE SAND

RECEIVED  
MAR 18 2011

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR\*\* USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE KCC WICHITA

Plugged through: CSG

District: 01

Signed

Stephen J Pfeifer  
(TECHNICIAN)

RECEIVED

MAR 14 2011

KCC DODGE CITY

Form CP-237