

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-20640-00-00  
Spot: E2W2NWNE Sec/Twnshp/Rge: 2-25S-17W  
649 feet from N Section Line, 1994 feet from E Section Line  
Lease Name: HAWES Well #: 1-2  
County: EDWARDS Total Vertical Depth: 4580 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	304		WITH 225 SX CMT
PROD	4.5	4579	2020	WITH 175 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/02/2011 1:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4360' & 4 SX CMT. PLUG AT 1160' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/02/2011 2:55 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4350' & 4 SX CMT WITH DUMP BAILER. 1ST PLUG AT 1160' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 330' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4480	4488		KINDERHOOK SA
4412	4418		MISSISSIPPI

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Richard M. Lacey  
(TECHNICIAN)

RECEIVED  
MAR - 8 2011  
KCC DODGE CITY

RECEIVED  
MAR 18 2011  
KCC WICHITA

Form 21-373