

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20563-00-00
Spot: SESESE Sec/Twnshp/Rge: 3-25S-17W
339 feet from S Section Line, 328 feet from E Section Line
Lease Name: MCKINNEY C Well #: 1-3
County: EDWARDS Total Vertical Depth: 4585 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4375		WITH 2 SX CMT
SURF	8.625	254		WITH 225 SX CMT
PROD	4.5	4584	2025	WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/10/2011 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4375' WITH 2 SX CMT. PLUG AT 1210' WITH 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/10/2011 11:10 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4375' WITH 2 SX CMT ON TOP WITH DUMP BAILER. 1ST PLUG AT 1190' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 280' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4425	4429		MISSISSIPPI

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL 3% CC BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
MAR 14 2011

KCC DODGE CITY

RECEIVED
MAR 18 2011
KCC WICHITA

Form CP-100