

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21206-00-00
Spot: SESWSE Sec/Twnshp/Rge: 2-24S-17W
364 feet from S Section Line, 1609 feet from E Section Line
Lease Name: MEALS Well #: 2-2
County: EDWARDS Total Vertical Depth: 4400 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	257		WITH 210 SX CMT
PROD	4.5	4394	2000	WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2011 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4220' & 4 SX CMT. PLUG AT 1080' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/16/2011 2:50 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMPED 50 SX CMT WITH 250# HULLS MIXED IN TO BOTTOM. TAGGED CMT TOP @ 4015'. 1ST PLUG AT 1090' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 290' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4277	4321		Mississippian

RECEIVED
MAR 21 2011
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL 3% CC BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
MAR 17 2011
KCC DODGE CITY

Form C-2-58