

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21868-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 1-25S-3E
1689 feet from S Section Line, 2313 feet from E Section Line
Lease Name: MOORE C Well #: 5
County: BUTLER Total Vertical Depth: 2726 feet

Operator License No.: 6407
Op Name: FLOWERS PRODUCTION CO., INC.
Address: PO BOX 249
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	205		
PROD	4.5	2726		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2010 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: LARRY STORM Company: CONSOLIDATED OILWELL SERVI Phone: (620) 431-9210

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/04/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH W/TBG CIRCULATING HOLE CLEAN @ 2270, DRILLING ON IRON, LAYED TBG DOWN, SDON. RAN MAGNET. PULLED LOTS OF METAL PIECES BACK OUT OF HOLE. RIH W/TBG @ 2270', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 40 SXS 60/40 POZMIX 4% GEL, 3% CC & DISPLACED IN CASING. TAGGED CEMENT @ 1838'. PRESSURED WELL, WOULD NOT HOLD. PUMPED FLAG, HOLE @ 1606'. RIH W/TBG @ 1587', CONSOLIDATED OILWELL SERVICES MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL, 3% CC AND DISPLACED IN CASING. TAGGED CEMENT @ 1486'. PRESSURED CASING, HELD OK. SHOT SQUEEZE HOLES @ 271'-272', SWEDGED INTO 4-1/2" CASING, CONSOLIDATED MIXED & PUMPED 118 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM, 3-16-2010. CEMENT TICKET #23315. 3-18-2010, RIH W/STRING LINE ON BACKSIDE OF CASING @ 175', DID NOT TAG CEMENT. 6-4-2010, CONSOLIDATED TAGGED CEMENT INSIDE 4-1/2" CASING @ 90', AND OUTSIDE 4-1/2" CASING @ 180'. NO FLUIDS IN HOLE, CONSOLIDATED MIXED & PUMPED 65 SXS POZMIX 2% GEL TO SURFACE. CEMENT CIRCULATED. CONSOLIDATED CEMENT TICKET #28475. P.A. COMPLETE 6-4-2010.

Remarks:

Plugged through: TBG

District: 02

Signed


(TECHNICIAN)

RECEIVED
Form CP-2/3

APR 05 2011

KCC WICHITA

JK