

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20490-00-00
Spot: NWNWSESW Sec/Twnshp/Rge: 31-32S-40W
1320 feet from S Section Line, 3833 feet from E Section Line
Lease Name: MCDONALD Well #: 1-31
County: MORTON Total Vertical Depth: 2424 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	630		WITH 370 SX CMT
PROD	4.5	2424	0	WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/17/2011 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: SHANE PELTON Company: HERMAN L. LOEB Phone: (618) 943-2227

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. MUD TO 1530'. 25 SX CMT AT 1530'. PERFORATE AT 650'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/17/2011 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 25 SX CMT & 35 7/8" NYLON BALL SEALERS (ALLIED FORGOT TO BRING HULLS). PUMP 7 BBL SPACER. PUMP 25 SX CMT AT 1550'. DISPLACE WITH WATER & PRESSURE TO 300#. RAN BOND LOG FROM 1050' TO 0'. TOC @ 1035'. PERFORATE AT 640'. CIRCULATE CASING & ANNULUS FULL OF CMT USING 225 SX CMT. CIRCULATED 25 SX CMT TO THE PIT.

Perfs:


Top	Bot	Thru	Comments
2364	2372		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
MAR 25 2011
KCC DODGE CITY

RECEIVED
MAR 30 2011
KCC WICHITA

Form 1-276