

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-00061-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 15-33S-11W
343 feet from S Section Line, 5107 feet from E Section Line
Lease Name: PAGE ESTATE A Well #: 1
County: BARBER Total Vertical Depth: 4610 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4500		
SURF	10.75	339		WITH 200 SX CMT
PROD	7	4610	0	WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/07/2011 12:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: DUMP 5 SX CMT ON CIBP. PERFORATE AT 600'. RUN TBG TO 600' & CIRCULATE HOLE FULL. TOOH WITH TBG. FILL ANNULUS & 7" WITH CMT WITH 15 SX GEL AHEAD.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/07/2011 4:50 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4500' WITH 5 SX CMT ON TOP OF CIBP. PERFORATE 7" CASING AT 600'. RUN TBG TO 600'. PUMPED DOWN TBG WITH 15 SX GEL & 100 SX CMT. 7" CASING CIRCULATED WITH CMT. SHUT IN 7" CASING HAD RETURNS UP 7" X 10 3/4" ANNULUS AT APP. 1/4 BPM. PRESSURED UP TO 500# & LOST RETURNS. LAID DOWN TBG. TIED SWEDGE INTO 7" CASING. PUMPED DOWN 7" CASING ESTABLISHED FAIR RETURNS @ 500#. PRESSURE CLIMBED TO 1850#. LOST RETURNS. PRESSURE HELD. RUN TBG BACK IN & CIRCULATED CMT OUT OF 7" CASING FROM 540' TO SURFACE TO BONG LOG & RE-PERFORATE OR ATTEMPT TO PULL SOME 7" CASING. PRIOR TO PROCEEDING ATTEMPT TO PUMP DOWN 7" X 10 3/4" ANNULUS ESTABLISHED CIRCULATION UP 7" CASING. WAIT ON MORE WATER. PUMP DOWN 7" X 10 3/4" ANNULUS WITH 310 SX CMT. CMT CIRCULATED OUT 7" CASING.

Perfs:

Top	Bot	Thru	Comments
4546	4570		MISSISSIPPIAN

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR & FAILED CSG TEST** USED 60/40 POZMIX 10% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED

MAR 14 2011

KCC DODGE CITY

RECEIVED
MAR 18 2011

KCC WICHITA