

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00237-00-00
Spot: NW Sec/Twnshp/Rge: 14-22S-32W
1309 feet from N Section Line, 1331 feet from W Section Line
Lease Name: PREISSER B Well #: 1
County: FINNEY Total Vertical Depth: 2766 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2630		WITH 2 SX CMT
SURF	8.625	530		WITH 350 SX CMT
PROD	5.5	2766	0	WITH 600 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/14/2011 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: SHANE PELTON Company: HERMAN L. LOEB Phone: (719) 340-8987

Proposed Plugging Method: SET CIBP @ 2630' WITH 2 SX CMT OR 200# HULLS & 30 SX CMT. LOAD HOLE WITH WATER. RUN BOND LOG TO DETERMINE TOC. PERFORATE IF NECESSARY. RUN TBG TO 200' & FILL 5 1/2" WITH CMT. 100 SX CMT DOWN ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/15/2011 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2630' WITH 2 SX CMT. RAN BOND LOG. TOC @ 85' FROM SURFACE. RUN TBG TO 2000'. CIRCULATE HOLE FULL OF CMT FROM 2000' TO 0' IN 2 STAGES USING 200 SX CMT. ATTEMPTED TO PUMP DOWN ANNULUS. COULD NOT IT WAS FULL.

Perfs:


Top	Bot	Thru	Comments
2756	2760		
2697	2705		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED

MAR 17 2011

KCC DODGE CITY

RECEIVED

MAR 28 2011

KCC WICHITA

Form C-223