

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20381-00-00
Spot: SESENEW Sec/Twnshp/Rge: 14-33S-33W
1250 feet from N Section Line, 2490 feet from W Section Line
Lease Name: FRENCH Well #: 1
County: SEWARD Total Vertical Depth: 2750 feet

Operator License No.: 6568
Op Name: KAISER-FRANCIS OIL COMPANY
Address: PO BOX 21468
TULSA, OK 74121

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	561		WITH 400 SX CMT
PROD	4.5	2745	0	WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/11/2011 11:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SAND FILL TO 1120'. RIH & TAG TOP OF FILL. SPOT 100# HULLS & 25 SX CMT. LET SET 4 HOURS & TAG TOC. PERFORATE 4 1/2" @ 600' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/11/2011 4:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

****WELL HAS CASING LEAK**** RIH WITH TBG & TAGGED TOP OF SAND AT 1118'. DROPPED ROCK IN ANNULUS & FOUND FL AT 450' IN BACKSIDE. PUMPED 100# HULLS & 25 SX CMT & SHUT IN 3 HOURS. TAGGED TOC @ 1020'. PUMPED 25 SX CMT AND SDON. 3/14/11: TAGGED TOC @ 365' IN 4 1/2" CASING. RIH W/ TBG TO 350' & FILLED 4 1/2" CASING WITH 30 SX CMT. TIED ONTO 4 1/2" X 8 5/8" ANNULUS & PUMPED 120 SX CMT IN TO ANNULUS AT 1.2 BPM @ 350#, PRESSURED TO 450 PSI. INITIAL SHUT IN PRESSURE AT 200 PSI.

Perfs:

Top	Bot	Thru	Comments
2605	2700		CHASE

RECEIVED
MAR 21 2011
KCC WICHITA

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
MAR 17 2011
KCC DODGE CITY

Signed Jack MacLashky
(TECHNICIAN)