

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-00471-00-00
Spot: NENESW Sec/Twnshp/Rge: 17-30S-32W
2426 feet from S Section Line, 2782 feet from E Section Line
Lease Name: WATKINS Well #: 1
County: HASKELL Total Vertical Depth: 2746 feet

Operator License No.: 32787
Op Name: KANSAS NATURAL GAS OPERATING, I
Address: 1200 MAIN ST PO BOX 818
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2714		
SURF	10.75	519		WITH 600 SX CMT
PROD	7	2745	0	WITH 900 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/15/2011 11:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PUMP 200# HULLS & 50 SX CMT AT 2650'. PLUG AT 1200' WITH 50 SX CMT. PLUG AT 540' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: PARTIAL
Date/Time Plugging Completed: 03/16/2011 11:00 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMPED 200# HULLS & 50 SX CMT AT 2650'. PLUG AT 1200' WITH 50 SX CMT. PLUG AT 540' WITH 50 SX CMT. GOOD CIRCULATION ON 1200' PLUG. WEAK CIRCULATION ON 540' PLUG, CMT DROPPING AFTER SHUT IN ON 540' PLUG. SDON. 3/16/11: TAGGED TOC @ 842'. PUMPED 50 SX CMT AT 540' WITH GOOD CIRCULATION. CMT HELD. TOPPED OFF WITH 20 SX CMT AT 60'. PUMPED 10 SX CMT DOWN 7" X 10 3/4" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
2730	2740		W/ 6 SHOTS P/FT
2682	2704		W/ 6 SHOTS P/FT
2650	2664		W/ 6 SHOTS P/FT

RECEIVED
MAR 21 2011
KCC WICHITA

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED
MAR 17 2011
KCC DODGE CITY

Form 08-23