

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-003-22687-00-00  
Spot: NWSWSENE Sec/Twnshp/Rge: 22-22S-19E  
3264 feet from S Section Line, 1036 feet from E Section Line  
Lease Name: EAST COOPER Well #: 22 E  
County: ANDERSON Total Vertical Depth: 864 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

| String | Size  | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| SURF   | 7     | 20         |             | 7 sx    |
| PROD   | 2.875 | 821        |             | 88 sx   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/21/2010 9:00 AM  
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.  
Proposal Rcvd. from: STERLING BARKER Company: \_\_\_\_\_ Phone: (785) 448-4816

Proposed Plugging Method: WORK STRING RUN TO BOTTOM, CEMENT TO SURFACE, SQUEEZE UNTIL DESIRED AMOUNT OF CEMENT AND PRESSURE IS ACHIEVED. CUT OFF PIPE 3 FT BELOW SURFACE AND BACKFILL.

Plugging Proposal Received By: LEVI SHORT WitnessType: PARTIAL  
Date/Time Plugging Completed 10/21/2010 11:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

Perfs:

RUN 1-INCH TUBING TO 864 FEET AND FILL TO SURFACE WITH CLASS A PORTLAND CEMENT THEN PRESSURE TO 1,500 POUNDS TO SHUT IN. A TOTAL OF 39 SACKS OF PORTLAND CEMENT WERE USED TO PLUG THE WELL.

RECEIVED  
JAN 20 2011 LS  
KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

RECEIVED

JAN 31 2011

KCC WICHITA

Form CP-2/3