

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-003-22713-00-00
Spot: NWSESWSE Sec/Twnshp/Rge: 22-22S-19E
651 feet from S Section Line, 1883 feet from E Section Line
Lease Name: EAST COOPER Well #: 29 E
County: ANDERSON Total Vertical Depth: 775 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	20		9 SX
PROD	2.875	825		93 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/23/2010 9:00 AM
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.
Proposal Revd. from: STERLING BARKER Company: _____ Phone: (785) 448-4816

Proposed Plugging Method: WORK STRING RUN TO BOTTOM, CEMENT TO SURFACE. SQUEEZE PLUG. CUT OFF PIPE 3 FT BELOW SURFACE AND BACKFILL.

Plugging Proposal Received By: LEVI SHORT WitnessType: PARTIAL
Date/Time Plugging Completed 11/23/2010 12:00 PM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TUBING TO 775 FEET AND FILL TO SURFACE WITH CLASS A PORTLAND CEMENT THEN PRESSURE TO 750 POUNDS TO SHUT IN. A TOTAL OF 55 SACKS OF PORTLAND CEMENT WERE USED TO PLUG THE WELL.

Perfs:

Top	Bot	Thru	Comments
802	808		7 SHOTS

RECEIVED

JAN 20 2011 LS

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)

RECEIVED
JAN 31 2011

Form CP-2/3

KCC WICHITA