

TO: ✓
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-003-21599-00-00
Spot: NWSWSWSE Sec/Twnshp/Rge: 15-21S-19E
555 feet from S Section Line, 2427 feet from E Section Line
Lease Name: ROGERS Well #: 2
County: ANDERSON Total Vertical Depth: 804 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.25	25		NO SXS LISTED
PROD	2.875	784		83 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/06/2010 10:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: STEVE BENJAMIN Company: _____ Phone: (785) 448-4804

Proposed Plugging Method: TIE TO 2 7/8" - ESTABLISH FLOW RATE & SQUEEZE CEMENT INTO FORMATION UNTIL DESIRED AMOUNT OF CEMENT AND PRESSURE IS ACHIEVED, FILLING WELL TO SURFACE. CUT OFF PIPE 3 FT. BELOW SURFACE, CUT, CAP AND BACKFILL.

Plugging Proposal Received By: LEVI SHORT Witness Type: NONE
Date/Time Plugging Completed: 10/06/2010 11:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

Perfs:

RUN 1-INCH PIPE IN 2-INCH PIPE AND PUMP CEMENT FROM TD (804 FEET) TO SURFACE. PULL PIPE THEN HOOK ON TO 2-INCH AND SQUEEZE CEMENT AT 500 PSI. A TOTAL OF 52 SACKS OF CEMENT WERE USED TO PLUG THE WELL.

RECEIVED

JAN 13 2011

LS

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed LS

(TECHNICIAN)

RECEIVED

JAN 31 2011 ✓

Form CP-2/3

KCC WICHITA