

TO: ✓  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-003-21604-00-00  
Spot: NESWSWSE Sec/Twnshp/Rge: 15-21S-19E  
575 feet from S Section Line, 1984 feet from E Section Line  
Lease Name: ROGERS Well #: 7  
County: ANDERSON Total Vertical Depth: 880 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.25	25		NO SXS LISTED
PROD	2.5	857		93 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/07/2010 10:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: STEVE BENJAMIN Company: \_\_\_\_\_ Phone: (785) 448-4804

Proposed Plugging Method: TIE TO 2 1/2"- ESTABLISH FLOW RATE & SQUEEZE CEMENT INTO FORMATION UNTIL DESIRED AMOUNT OF CEMENT AND PRESURE IS ACHIEVED, FILLING WELL TO SURFACE. CUT OFF PIPE 3 FT. BELOW SURFACE, CUT, CAP AND BACKFILL.

Plugging Proposal Received By: LEVI SHORT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed 10/07/2010 2:00 PM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH PIPE IN 2-INCH PIPE AND PUMP CEMENT FROM TD (880 FEET) TO SURFACE. PULL PIPE THEN HOOK ON TO 2-INCH AND SQUEEZE CEMENT AT 750 PSI. A TOTAL OF 55 SACKS OF CEMENT WERE USED TO PLUG THE WELL.

Perfs:

Top	Bot	Thru	Comments
798	812		

RECEIVED  
JAN 13 2011 LS  
KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed L. Duss

(TECHNICIAN)

RECEIVED Form CP-2/3  
JAN 31 2011 ✓  
KCC WICHITA