

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22150-00-00
Spot: NENWNE Sec/Twnshp/Rge: 25-7S-18W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease Name: JONES Well #: 2
County: ROOKS Total Vertical Depth: 3280 feet

Operator License No.: 34179
Op Name: THOMAS M. BROWN LLC
Address: PO BOX 250
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1212	0	425 SX
COND	13.38	91	0	125 SX
PROD	5.5	3254	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/26/2011 9:00 AM
Plug Co. License No.: 33868 Plug Co. Name: RENEGADE WELL SERVICE LLC
Proposal Rcvd. from: JAKE BROWN Company: THOMAS M. BROWN LLC Phone: (785) 737-7070

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 600# hulls.
Backside squeezed with 225 sxs. Casing leak at 2196'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/26/2011 11:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2500' - pumped 110 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled tubing to 2200' - pumped 180 sxs 60/40 pozmix - 4% gel with 300# hulls to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing with 35 sxs 60/40 pozmix - 4% gel.
Will check backside when operator cuts.

Perfs:

Top	Bot	Thru	Comments
3170	3174		
3141	3143		
3136	3138		
3031	3033		
2940	2942		
2923	2925		

RECEIVED
FEB 04 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #41774.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM

Form CP-2/3

FEB 02 2011