

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-049-20899-00-00
Spot: E2SENE Sec/Twnshp/Rge: 22-30S-10E
4326 feet from S Section Line, 113 feet from E Section Line
Lease Name: BAUDER Well #: 1
County: ELK Total Vertical Depth: 2025 feet

Operator License No.: 3591
Op Name: TRIBOULET, ED DBA C & E OIL CO.
Address: RR1 BOX 1B2
MOLINE, KS 67353

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/19/2010 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: Company: Phone:

Proposed Plugging Method: 50' plug at TD, 50' plug at 1100' and 550' to surface. Perforate at 1100' and 550'.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 04/20/2010 5:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 2000' gelled hole and spotted 10 sack plug. Pulled 1" and perforated at 1100' and 550'. Ran 1" to 1100' and spotted 5 sack plug. Pulled 1" up to 550' and circulated cement inside and outside casing to surface. Pulled 1" and topped well off. A total of 142 sacks of cement were used to plug this well.

Perfs:

RECEIVED

FEB 8 2011 DAS

KCC Chanute Dist. #3

RECEIVED

FEB 11 2011


KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)