

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-049-20277-00-00
Spot: S2S2NWNW Sec/Twnshp/Rge: 12-31S-8E
4059 feet from S Section Line, 4561 feet from E Section Line
Lease Name: SHRADER Well #: 16
County: ELK Total Vertical Depth: 1730 feet

Operator License No.: 3591
Op Name: TRIBOULET, ED DBA C & E OIL CO.
Address: RR1 BOX 1B2
MOLINE, KS 67353

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/02/2010 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' plug at TD, 50' plug at 900' and 550' to surface. Perforate at 900' and 550'.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 06/03/2010 5:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1700' gelled hole and spotted 15 sack plug. Pulled 1" and perforated at 900' and 550'.
Ran 1" to 900' and spotted 15 sack plug. Pulled up 550' and circulated cement inside and
outside of casing to surface. Pulled 1" and topped well off. A total of 110 sacks of cement were
used to plug this well.

RECEIVED

JAN 27 2011 DAS

KCC Chanute Dist #3


RECEIVED
FEB 11 2011
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)