

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.


OPERATOR Cattlemans Oil Operations API NO. 15-051-22,762-0000
 ADDRESS Catherine Rt. Box 32 COUNTY Ellis
Hays, Kansas 67601 FIELD Polak
 **CONTACT PERSON Leo R. Dorzweiler LEASE Polifka
 PHONE 913 6257000

PURCHASER Inland Crude WELL NO. 1
 ADDRESS Wichita, Kansas WELL LOCATION E/2 NW SE
660 Ft. from north Line and
 990 Ft. from west Line of

DRILLING CONTRACTOR Thunderbird Drilling, Inc. the E/4 SEC. 8 TWP. 13S RGE. 18W
 ADDRESS P.O. Box 18407 13S 18W
Wichita, Kansas 67202 WELL PLAT KCC DPW

PLUGGING CONTRACTOR _____
 ADDRESS _____

TOTAL DEPTH 3810' PBTD _____
 SPUD DATE 12/18/81 DATE COMPLETED 1-1-82
 ELEV: GR _____ DF _____ KB 2164



DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS
 Report of all strings set — surface, intermediate, production, etc. (New)/(Used) casing. MISC. _____

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8"	24#	266'	com	160	2% gel, 3% cc.
Production		5 1/2"	11#	3801	ASC	125	

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	jet	3506-09
TUBING RECORD				jet	3494-96
Size	Setting depth	Packer set at			
2 7/8	3625				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
1000 gallons 15% regular	3506-09 3494-96

TEST DATE:		PRODUCTION			
Date of first production	Producing method (flowing, pumping, gas lift, etc.)	A.P.I. Gravity		Gas-oil ratio	
2-27-82	pumping	32			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	21 bbls.	none	70 MCF		
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
			3506-09 3494-96		

** The person who can be reached by phone regarding any questions concerning this well is Leo R. Dorzweiler. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

RECEIVED
 KANSAS CORPORATION COMMISSION
 WICHITA, KANSAS
 4 1982
 CONSERVATION DIVISION
 Wichita, Kansas

Name of lowest fresh water producing stratum unknown Depth 216'
 Estimated height of cement behind pipe: Cement Circulated

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Anhydrite	1454			
Topeka	3181			
Heebner	3420			
Lansing	3466			
Weathered Arb.	3732			
Arbuckle	3783			
T D	3810			

DST # 1 Strong Building
 Blow Through out test
 400' gassy oil cut mud 120'
 Heavy oil & gas cut mud 420'
 oil & gas cut water 240'
 water
 BF 99-357# 45 Min
 ISD 1115# 45 Min
 FF 396-545# 45 Min
 FSD 1086# 45 Min
 DST # 2 Strong Blow
 1770' Salt water

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T

STATE OF Kansas, COUNTY OF Ellis SS,

Leo R. Dorzweiler OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS Owner FOR Cattlemans Oil OPERATOR OF THE Polifka LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 10 DAY OF March 19 82, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Leo R. Dorzweiler
 SUBSCRIBED AND SWORN TO BEFORE ME THIS 26th DAY OF April 19 82

BETTY CREWS
 Ellis County, Ks.
 Not. Exp. 8-16-84

Betty Crews
 NOTARY PUBLIC
 (Betty Crews)

MY COMMISSION EXPIRES: August 16, 1984