

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22256-00-00
Spot: S2N2N2NE Sec/Twnshp/Rge: 17-17S-27W
486 feet from N Section Line, 1320 feet from E Section Line
Lease Name: WATERSON "A" Well #: 1-17
County: LANE Total Vertical Depth: 4680 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 12
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	230		WITH 165 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/09/2010 10:15 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: RICH WHEELER Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 2190' WITH 50 SX CMT. 2ND PLUG AT 1290' WITH 80 SX CMT. 3RD PLUG AT 630' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: NONE
Date/Time Plugging Completed: 10/09/2010 12:15 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

1ST PLUG AT 2190' WITH 50 SX CMT. 2ND PLUG AT 1290' WITH 80 SX CMT. 3RD PLUG AT 630' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
OCT 13 2010
KCC DODGE CITY

Signed

Jerry W. Stapleton
PART II

(TECHNICIAN)

RECEIVED
OCT 15 2010

Form CP-2/3

KCC WICHITA