

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-40134-00-00
Spot: NWNENW Sec/Twnshp/Rge: 29-23S-4E
330 feet from N Section Line, 1650 feet from W Section Line
Lease Name: FERRIER-EVERETT Well #: 2
County: BUTLER Total Vertical Depth: 2089 feet

Operator License No.: 7131
Op Name: MORRIS, RICHARD B.
Address: PO BOX 482
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	83		43 SX
PROD	4.5	2045		50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/23/2010 8:00 AM
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC
Proposal Rcvd. from: RICHARD MORRIS Company: RICHARD MORRIS Phone: (620) 877-7094

Proposed
Plugging
Method:

PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE
Date/Time Plugging Completed: 08/24/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2055', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 50 SXS CLASS A COMMON 3% CC AND DISPLACED IN CASING. PULLED TBG @ 1000'. TAGGED CEMENT @ 1964'. W/TBG @ 1000', CONSOLIDATED MIXED & PUMPED 25 SXS CLASS A COMMON 3% CC AND DISPLACED IN CASING. RIH ON WIRELINE, PERFORATED CASING @ 253'-254'. 8-24-2010, TAGGED CEMENT @ 870'. SWEDGED INTO 4-1/2" CASING, CONSOLIDATED ESTABLISHED CIRCULATION & PUMPED 105 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 8-24-2010, 5:00 P.M. CONSOLIDATED CEMENT TICKET #28579.

Perfs:

Top	Bot	Thru	Comments
2016	2089	CSG	

RECEIVED
NOV 02 2010
KCC WICHITA

Remarks: CASING LEAK @ 1000'-1800'

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)