

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-04897-00-01  
Spot: SWNWSW Sec/Twnshp/Rge: 15-20S-12W  
1650 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: MILLER Well #: 1  
County: BARTON Total Vertical Depth: 3450 feet

Operator License No.: 3942  
Op Name: MONROE, ORVILLE DBA BIG "O"  
Address: 2820 PASEO DR  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	247	0	250 SX
PROD	5.5	3450	0	50 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/28/2010 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: ORVILLE MONROE Company: BIG "O" Phone: (620) 793-2134

Proposed Well was plugged in 1998 - washed down in 07/03/2010.  
Plugging Ordered 275 sxs 60/40 pozmix - 4% gel - 500# hulls - 15 sxs gel.  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/28/2010 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3300' - pumped 15 sxs gel - followed with 50 sxs cement and 200# hulls.  
Pulled tubing to 1500' - pumped 90 sxs cement with 200# hulls.  
Pulled to 660' - pumped 50 sxs cement.  
Pulled tubing to 300' - circulated to surface with 35 sxs.  
Pulled tubing - topped off with 15 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3430	3434		
3372	3376		
3340	3344		
3326	3332		
3293	3299		
3230	3234		
3204	3207		
3184	3190		

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

District: 04

RECEIVED

OCT 08 2010  
10-8-10  
KCC WICHITA

(TECHNICIAN)

CM

Form CP-2/3

OCT 04 2010