

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-20941-00-00  
Spot: S2NWNWSE Sec/Twnshp/Rge: 24-15S-34W  
2240 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: MCDANIEL D Well #: 1-24  
County: LOGAN Total Vertical Depth: 4780 feet

Operator License No.: 3293  
Op Name: RUSSELL OIL, INC.  
Address: PO BOX 8050  
EDMOND, OK 73083

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	225		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/01/2010 12:00 AM  
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC  
Proposal Rcvd. from: STEVE RUSSELL Company: RUSSELL OIL, INC. Phone: (620) 770-2214

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE  
Date/Time Plugging Completed: 11/01/2010 5:15 AM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st. Plug at 2360' w/25 sxs.  
2nd. Plug at 1250' w/100 sxs.  
3rd. Plug at 275' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.

Perfs:

Remarks: CONSOLIDATED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Ed Schumacher  
(TECHNICIAN)

CM

RECEIVED

NOV 17 2010 Form CP-2/3

KCC WICHITA

NOV 12 2010