

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-05197-00-02
Spot: SESWNE Sec/Twnshp/Rge: 17-1S-34W
2792 feet from S Section Line, 1733 feet from E Section Line
Lease Name: TEXACO CAHOJ Well #: 37 INJ
County: RAWLINS Total Vertical Depth: 4287 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 447 | 0 | 400 SX |
| PROD | 5.5 | 4320 | 0 | 250 SX |

Well Type: EOR UIC Docket No: E16643.15 Date/Time to Plug: 06/23/2010 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 1200# hulls - 5 sxs c.c. - 10 sxs gel spacer.
Casing leaks 2933' - 2995'. CIBP at 3954'.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/23/2010 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3930' - pumped 10 sxs gel spacer - followed with 80 sxs 60/40 pozmix - 4% gel - 2 sxs c.c. and 375# hulls.
Pulled to 2890' - pumped 150 sxs 60/40 pozmix - 4% gel - 3 sxs c.c. and 525# hulls.
Pulled to 1442' - pumped 150 sxs 60/40 pozmix - 4% gel with 300# hulls to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing with 15 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 5 1/2" annulus - pumped 15 sxs 60/40 pozmix - 4% gel.
S.I.P. 100#.

Perfs:

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 02 2010
CONSERVATION DIVISION
WICHITA KS

Remarks: SWIFT CEMENTING COMPANY-TICKET #18019. LEASE ORIGINALLY KNOWN AS A.S. CAHOJ #4.

Plugged through: TBG

District: 04

Signed

Pat Bedore
(TECHNICIAN)

CM

Form CP-2/3

JUN 30 2010

SKELLY OIL COMPANY

#1 A S CAHOJ

17-1-34W
SE SW NE

Contr. C WENTWORTH

RAWLINS County


E 3111 Comm. 11-12-59 Comp. 12-25-59 IP 235 BOPD

| Tops | Depth | Datum |
|-------|-------|-------|
| ANH | 2944 | +167 |
| OREAD | 3890 | -779 |
| LANS | 3991 | -880 |
| B/KC | 4260 | -1149 |
| MARM | 4290 | -1179 |
| TD | 4330 | -1219 |

Casing
8" 447
5" 4320

PERF 4229-37: ACID 500: SWB
206 BO, NW/4 HR

CAHOJ POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS