

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01805-00-00
Spot: S2SWSW Sec/Twnshp/Rge: 34-8S-16W
330 feet from S Section Line, 4620 feet from E Section Line
Lease Name: SWISHER Well #: 1
County: ROOKS Total Vertical Depth: 3247 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	93	0	w/50 sxs cmt
L1	4.5	3315		
PROD	7	3056	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/26/2010 2:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITCHMAN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-5100

Proposed Plugging Method: Ordered out 450 sxs 60/40 pozmix - 4% gel - 1000# hulls.
Casing parted at 1800' - unable to repair - decided to P/A.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/26/2010 7:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2800'. Copeland pumped 150 sxs 60/40 pozmix - 4% gel - 3% c.c. w/300# hulls.
Pulled tubing to 1800' - pumped 150 sxs cement with 300# hulls.
Pulled to 875' - pumped 125 sxs cement with 300# hulls - circulated cement.
PTOH. Topped off 7" casing with 15 sxs cement - casing full.
Hooked up to backside and pumped instant 250#.

Perfs:

Top	Bot	Thru	Comments
3096	3247		LKC

RECEIVED
AUG 31 2010

Remarks: COPELAND ACID AND CEMENTING COMPANY.

KCC WICHITA

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

AUG 27 2010