

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21358-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 24-20S-16W
1692 feet from S Section Line, 2335 feet from E Section Line
Lease Name: NBA Well #: 1-24
County: PAWNEE Total Vertical Depth: 3940 feet

Operator License No.: 3942
Op Name: MONROE, ORVILLE DBA BIG "O"
Address: 2820 PASEO DR
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3816		
SURF	8.625	1101		WITH 375 SX CMT
PROD	5.5	3933	2100	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/30/2010 2:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3750' & 5 SX CMT. PLUG AT 1140' WITH 15 SX GEL & 50 SX CMT. PLUG AT 450' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/30/2010 4:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3720' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 1140' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 450' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3832	3841		
3827	3830		
3820	3824		
3810	3812		
3800	3808		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED
OCT -7 2010
KCC DODGE CITY

RECEIVED
OCT 19 2010
KCC WICHITA